Sl. No.	
1	Earth work excavation by manual means in hard soil involving an average horizontal thro meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dress disposed earth to be leveled neatly after breaking of clods etc complete as per specificati directions of engineer in charge of the work
2	Removing B.S Slab of Drain and stacking etc complete as per specifications and directions of e in charge of the work
3	Refixing stone slabs of drains and pointing in C.M (1:3) etc complete as per specificatio directions of engineer in charge of the work
4	Providing, laying, spreading and compacting graded stone aggregate to **wet mix mac** specification including premixing the Material with water at OMC in mechanical mix plant carri mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course o prepared surface and compacting with vibratory roller to achieve the desired density etc comple per specifications and directions of engineer in charge of the work
5	Cleaning the existing WBM road surface including removing of binding materials and other for matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting old gunny bags and / or compressed air to receive bituminous treatment including cost of all mater labour, HOM of machineries, curing etc complete as per specifications and directions of enginee charge of the work
6	Providing and applying primer coat with bitumen emulsion on prepared surface of granular ba including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechani means etc complete as per specifications and directions of engineer in charge of the work
7	Providing and laying **semi dense bituminous concrete** 25mm thick with 100-120 TPH batch typ HMP producing an average output of 75 tonnes per hour using crushed aggregates of specifie grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to wo site, laying with a hydrostatic paver finisher with sensor control to the required grade, level an alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compactio as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. **Wit 80/100 grade bitumen,** etc complete as per specifications and directions of engineer in charge of the work
8	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km etc complete as per specifications and directions of engineer in charge of the work
	Total
	KRIDLService charge and Applicable Taxes @ 11%
	Third Party Inspection Charges @ 1%
	Grand Total

CERTIFICATE

1. Certified that the above work done satisfactory and no materials issued from departmentally.

Sadha

Previous Measurement		Present Measurement			Total Upto Date		Remarks
Qty.	Cost	Qty.	Rate Rs. P.	Amount	Qty	Cost	
-	-	511.25	90.72	46381.00	511.25	46381.00	
-	-	567.00	50.11	28412.00	567.00	28412.00	
-	-	567.00	70.04	39713.00	567.00	39713.00	
-	-	496.40	1121.04	556484.00	496.40	556484.00	
-	-	2131.00	10.53	22439.00	2131.00	22439.00	
-	-	2131.00	44.28	94361.00	2131.00	94361.00	
-	-	53.28	9631.44	513163.00	53.28	513163.00	
-	-	511.25	72.71	37173.00	511.25	37173.00	
				1338126.00		**1338126.00**	
				147193.86		**147193.86**	
				13381.26		**13381.26**	
				1498701.12		**1498701.12**	

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಧಿಯಂತರರು.
ವಿದ್ಯಾರಣ್ಯಪುರ ಉಪ ವಿಭಾಗ
ಯಲಹಂಕ ವಲಯ,
ಬೃ. ಬೆಂ. ಮ. ಪಾ., ಬೆಂಗಳೂರು-97